

PART NUMBER
WPS UTPS-MEG-50-20-20-CHD

JOB NAME

IMAGE	DESCRIPTION		
	Underground temporary pole service assembly. MEG Approved. 1-50amp 240v receptacle, 2-20amp 120v receptacles.		
	COMPONENTS		
	QTY.	MANUFACTURER	PRODUCT
	1	CUTLER HAMMER	CHR1G9N9NS MEG Temp Power Pedestal
	5'	PVC	1-1/4" Sch 40 Conduit
	1	PVF	1-1/4" Terminal Adaptor
	1	ARLINGTON	404 Steel Locknut 1-1/4"
	1	ARLINGTON	443 Plastic Bushing 1-1/4"
	2	STEEL CITY	6H3-B Conduit Hanger 1-1/4" -1-1/2" EMT
	20'		2-UD-M Stephens Triplex
	1	MISC	4"x4"x8' Treated Pole
	6		J1220ACHZ HWH SMS Slot 12x1-1/4" Screw
	4		J25WUSSZ Flat Washer
	4	MADISON	162 1-Hole Strap 1/8"
	1		5/8" x 8' ZZ588 Galvanized Ground Rod
	1		5/8" Ground Rod Clamp
	7'		6-Bare-M Solid Bare Copper
1	MISC	White Phasing Tape On Yellow Conductor of 2UD Cable – Both Ends; Noalox; (3) Ty-Wraps to Secure Ground Rod to Post	

NOTES

WPS	UTPS	-MEG	-50-20-20	-CHD
PART NO. PREFIX	ASSEMBLY TYPE	MEG DESIGNATION	DISTRIBUTION	MANUFACTURER
	UNDERGROUND TEMPORARY POLE SERVICE ASSEMBLY	METER EQUIPMENT GROUP APPROVED	1-50AMP 240V REC 2-20AMP 120V REC	CUTLER HAMMER