

IPL Cochrane Extraction Plant – DEHY Drain Lines



Client	Location	Project	Value
Inter Pipeline	Cochrane Extraction Plant	DEHY Drain Lines	\$32K
Start Date: November 2018		Finish Date: November 2018	
<p>Project Description:</p> <p>Project Goal: Install 1" drain line from DEHY Unit A to DEHY Unit B to allow liquids to be pushed from one unit to the other during recycling of DEHY beds (every 36 hrs).</p> <p>OCL's Scope: Fabricate and install new process piping and structural to tie-in the new drain piping to existing process piping.</p> <p>Constructability review and upfront planning of project</p> <ul style="list-style-type: none"> ▪ General Contractor - management of all sub-contractors ▪ Budget development, develop and manage project scheduling ▪ Procurement of materials & equipment ▪ Fabricate and install 60' of 1" XS carbon pipe and 2 – tapped 6" tapped hub blinds ▪ Assist with unit shut down, unit start-up and commissioning ▪ Isolation of unit for outage, removal of unit isolation ▪ Install new tie-in flanges <p>Project Statistics:</p> <p>40+ diameter weld inches of carbon pipe 325+ onsite manhours, 0 incidents Completed on time, on budget, <1% rework, 0 weld failures</p>		 	