

Kearl NODA Wedge



Client	Location	Project	Value
North American Production Products	Kearl Oilsands	NODA Wedge	\$12.2M
Start Date: June 2018		Finish Date: September 2018	
<p>Project Description:</p> <p>This project consisted of 1.8km of a civil corridor, piling, structural steel and pipeline construction. Two pipelines were constructed for the project, a 6" gland water line and a 30" course tailings line. The 30" course tailings line also incorporated several Y-Lateral installations, drain valves, and large diameter bolt ups. The Project also required a new HDPE drainage system to be tied into existing dyke wall drainage.</p> <ul style="list-style-type: none"> ▪ 100,000 cubic meters of civil material moved & placed ▪ 1.8 km of 30" and 6" carbon Steel piping respectively ▪ 1 km of 12" HDPE DR 11 ▪ 75, 24" driven piles ▪ 500m of half culvert installation <p>Subcontractors included: Survey & Geomatics, Non-Destructive Testing, Piling, Structural Steel Fabricators, Horizontal Directional Drilling, Insulation and Hydro Testing.</p> <p>Project Statistics:</p> <ul style="list-style-type: none"> ▪ 56,300 Man Hours ▪ Completed one month ahead of schedule ▪ 0 Medical Aids ▪ Kearl CMT Letter of achievement 		 	