

Keyera KJT Nitrogen Offload



Client	Location	Project	Value
Keyera	Keyera Josephburg Terminal	KJT Nitrogen Offload	\$250K
Start Date: February 2018		Finish Date: April 2018	
<p>Project Description:</p> <p>This project consisted of installing a nitrogen purge skid and connecting it to an existing incinerator (mechanical and E&I). Scope of work was expanded to include shutdown piping for operations.</p> <p>Piles were cut and caps welded to grade in preparation for N2 skid. N2 was received and installed. Piping was prefabricated and coated before being received and installed on site. Engineering changed the SoW due to incinerator issues resulting in some piping and electrical cable to be removed and stored onsite for future install. Electrical and instrumentation subcontractor installed cabling, instruments, and panels for added controls, monitoring and lighting.</p> <ul style="list-style-type: none">▪ Total Exposure Hours: 1,574▪ Number of Incidents (FA, MA, LTI): 0▪ Quality Repair Rate: 0%▪ Project finished ahead of schedule, adapting to increases and changes to SoW		 	