

# Syncrude Weir EPC



Client	Location	Project	Value
Syncrude	Base Mine	BML Weir Skimmer	\$500K
<b>Start Date:</b> September 2017		<b>Finish Date:</b> May 2018	
<p><b>Project Description:</b></p> <p>Client needed to remove residual oil/bitumen from their settling pond.</p> <p>OCL designed a weir box with two adjustable skimmers to attach to an existing barge utilizing limited work space and attachment points. OCL worked closely with the client to meet all requirements while following client standards and specifications (eg./ no welding on barge).</p> <p>Post design, OCL procured the material, fabricated, assembled, and fit up (including inspections and testing) two weir box assemblies. Completed assemblies were shipped to OCL yard and stored until the water on the settling pond no longer has ice at which point OCL will install the weir boxes and skimmers.</p>			