

How to build a 220 for Sercel

Quantity	Description	Each Cost	Total Cost
2	Sercel Supplied guns		\$0.00
8	Bumper pads 3" D bumper	\$65.25	\$522.00
1	* Umbilical (100')	\$14,500.00	\$14,500.00
2	Timing Jumpers	\$450.00	\$900.00
2	Firing Jumpers	\$450.00	\$900.00
1	Spiders	\$2,500.00	\$2,500.00
1	Flotation Buoys	\$11,250.00	\$11,250.00
3	3/4" 2 1/2" Bolts and nylock nuts	\$9.38	\$28.14
1	Buoy Cage	\$4,125.00	\$4,125.00
32	3/8" X 1 1/2" Bolts and nylock nuts	\$8.44	\$270.08
1	Interface Box (J Box)	\$1,000.00	\$1,000.00
8	3/4" X 3.5" bolts and nuts	\$9.38	\$75.04
8	7/8" Shackles	\$97.50	\$780.00
1	Hydrophone	\$690.00	\$690.00
1	50' tow member	\$575.00	\$575.00
4	7/8" Swivel	\$333.50	\$1,334.00
1	Concrete hose	\$156.25	\$156.25
3	Concrete hose Clamps	\$189.00	\$567.00
1	Labor	\$2,100.00	\$2,100.00
0.5	2" electrical tape (Case)	\$312.50	\$156.25
0.5	2" Bulldog Tape (Case)	\$312.50	\$156.25
1	Safety wire	\$62.50	\$62.50
1	** Vendor delivery costs	\$500.00	\$500.00
	Actual cost		\$43,147.51
	Total purchase price inc 10% discount		\$38,000.00

* Hydrostatic testing of Umbilical should be done at least once per year

** Vendor delivery costs are used to transport equipment to and from other vendors. This is not a delivery charge! (i.e. to and from powder coating and other testing facilities)

Offsite labor for Mobilizing equipment or training clients is billed at \$2,000 per day

Prices subject to change. All costs are quoted in USD

A Deposit of 50% of the purchase price is required to start the build out process. Total build out time is Six (6) weeks from A.R.O. & deposit. Expedited orders are accepted on a case by case basis and may incur a 10% expediting fee. (please let us know your time table as we do keep some equipment on the shelves)