



Project No. 25: Fir Mountain to Pine Grove

Estimated Project Cost: \$2,202,550

Project Priority: Medium

Project Description

A total of 9,800ft of 8-in diameter waterline will be installed along Fir Mountain Road and Wells Drive, beginning at Thomsen Road and ending at Pine Grove Reservoir, replacing existing 4-in waterline. The upsized waterline will replace pipe at the end of its usable life and improve fire flows, redundancy, and distribution capacity to Pine Grove and the northern parts of the District. To maintain two pressure zones, a new PRV station will be installed along the Wells Drive, near Pine Grove Reservoir.



Upsized Waterline	Relief Valve	Crystal Spring	Highway/Road
New Waterline	Hydrants	Existing Waterline	Property line
New PRV	Existing Reservoir		Water
New Reservoir			
PRV Existing			

0 1,000 Feet

