

ADDENDUM NO. 1

SYRACUSE HOUSING AUTHORITY
AMP 71-04

SECTION 8 SATELLITE OFFICES
AT CENTRAL VILLAGE
203 MARTIN LUTHER KING BLVD EAST

RSA PROJECT #2011

February 4, 2021

ROBERTSON STRONG APGAR ARCHITECTS, P.C.
1054 JAMES STREET
SYRACUSE, NY 13203

ALL CONTRACTORS:

Contractors submitting proposals for the above projects shall include the following changes, additions, deletions, interpretations, etc. of the Drawings and Specifications to the Base Bid, Alternate Bid, and Substitution Bid Proposals. All Addenda shall become part of the contract.

GENERAL:

1. At all new split A/C units in offices: Provide and install break metal enclosure in corner below units to conceal all new piping. Size to be 4" x 4" and extend from floor to bottom of unit. Color to be white. Attach to walls with tamper resistant fasteners.
2. The following color selections have been made by the owner:
Paint Color 1 (Doors): SW 6993 Black of Night (Satin)
Paint Color 2 (Walls): to match PPG1001-3 Thin Ice (Satin)
Paint Color 3 (Frames and Kitchen Cabinets): SW7006 Extra White (Satin)
Paint Color 4 (Ceilings): SW7007 Ceiling Bright White
VCT: Armstrong Standard Excelon – Imperial Texture Classic White
Vinyl Base: White

SPECIFICATIONS: No Change

DRAWINGS:

1. Drawing M100, Detail 52 – Saddle clams to attach PVC condensate pipe to the wall shall be installed every 4' maximum, and at every elbow.

END OF ADDENDUM NO. 1